ES26-085 Arfa Yapi - Block A1, Bayrakli, Izmir: quantities (QS-01)

Nudura ICF supply - quantities as priced (forms + 3 % spares, accessories + 2.5 % spares). Quotation, not for construction.

1. Nudura forms (delivered full, cut on site)

Item	One block	All 12 blocks
Nudura 6in Standard 90° corner	116	1,392
Nudura 6in Standard straight	468	5,616
Nudura 8in Standard 90° corner	141	1,692
Nudura 8in Standard straight	634	7,608
Total forms	1,359	16,308

2. Accessories

Item	One block	All 12 blocks
Form-Lock (6in Standard) (NUS-ABLOK-06)	154	1,848
Form-Lock (8in Standard) (NUS-ABLOK-08)	241	2,892
Spray Foam Cans (NUS-SF-BOX)	78	936
T-Form Support Straps (NUS-ATSTP-00)	460	5,520
Vertical Joint Clips (NUS-A0VJC-00)	4,800	57,600
End Caps (6in Standard) (NUS-A0ECF-06)	111	1,332
End Caps (8in Standard) (NUS-A0ECF-08)	755	9,060
Lintel Closures (6in Standard) (NUS-PLINT-06)	16	192
Lintel Closures (8in Standard) (NUS-PLINT-08)	179	2,148

3. Alignment system (TBC)

Item	One block	All 12 blocks
Alignment systems (corner + spacing)	71 (6 + 65)	71
Stillages (20 systems each) - reused level to level and block to block	4	4

4. Concrete

Item	One block (m^3)	All 12 blocks (m^3)
ICF core fill (net of openings)	222.9	2,674.9
ICF core fill + 5 % pump / waste	234.1	2,808.7
By others (information): RC slabs / balconies / stairs	283.8	3,405.2

5. Shipping (haulage TBC)

Item	One block	All 12 blocks
Form pallets	22	264
40 ft containers (estimated 5-6 per block)	5-6	60-72